Proposal: 260303 **Let Date:** November 19, 2026 **Call Order:** 044

J/P Num: 36893(04) **Proj. Num:** IN-MC-78

38909(04) IN-MC-80

Counties: MCINTOSH, PITTSBURG

Description: BRIDGE REHABILITATION
INDIAN NATION TURNPIKE/SH-375 (OTA ACCESS): OVER SOUTH CANADIAN RIVER AND OVERFLOW, 8.6 MILES SOUTH OF THE SH-9 INTERCHANGE NEAR VERNON.
PROJECT LENGTH = 0.894 MILES

	Line #		Item Description	Quantity	Unit
0001	ROADWAY - IN-MC-78				
	0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
	0020	202(A)2200	UNCLASSIFIED EXCAVATION	400.000	CY
	0030	202(D)2500	UNCLASSIFIED BORROW	530.000	CY
	0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
	0050	221(B)2300	TEMPORARY SILT FENCE	990.000	LF
	0060	230(A)7200	SOLID SLAB SODDING	2,105.000	SY
	0070	233(A)0200	VEGETATIVE MULCHING	0.350	AC
	0080	241 3100	MOWING	0.700	AC
	0090	307(K)4200	STABILIZED SUBGRADE	604.000	SY
	0100	310(B)5300	SUBGRADE, METHOD B	100.000	SY
	0110	407(B)7300	TACK COAT	77.000	GAL
	0120	408 8100	PRIME COAT	335.000	GAL
	0130	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	187.000	TON
	0140	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	115.000	TON
	0150	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	453.000	LF
	0160	413(C)4400	RUMBLE STRIP-METHOD PCC-CON	120.000	LF
	0170	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	100.000	SY
	0180	414(G)5800	P.C. CONCRETE FOR PAVEMENT	14.000	CY
	0190	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	100.000	SY
	0200	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	4,530.000	SY
	0210	619(B)6396	REMOVAL OF GUARDRAIL	430.000	LF
	0220	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	325.000	LF
	0230	623(G)1820	GUARDRAIL END TREATMENT (31")	1.000	EA
	0240	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	3.000	EA
	0250	625(B)4300	REMOVE AND RECONSTRUCT FENCE	240.000	LF
	0260	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	14.000	EA

Proposal: 260303 **Let Date:** November 19, 2026 **Call Order:** 044
J/P Num: 36893(04) **Proj. Num:** IN-MC-78
38909(04) IN-MC-80
Counties: MCINTOSH, PITTSBURG
Description: BRIDGE REHABILITATION
INDIAN NATION TURNPIKE/SH-375 (OTA ACCESS): OVER SOUTH CANADIAN RIVER AND OVERFLOW, 8.6 MILES SOUTH OF THE SH-9 INTERCHANGE NEAR VERNON.
PROJECT LENGTH = 0.894 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE - IN-MC-78			
0270	501(G)1800	CLSM BACKFILL	10.000	CY
0280	504(A)5200	APPROACH SLAB	76.200	SY
0290	504(B)5300	SAW-CUT GROOVING	3,038.500	SY
0300	504(E)5500	CONCRETE PARAPET	61.350	LF
0310	509 0100	SPECIAL CONCRETE FINISH	1,323.000	SY
0320	509(A)0210	CLASS AA CONCRETE	691.700	CY
0330	509(B)0320	CLASS A CONCRETE	20.000	CY
0340	509(D)0510	CLASS C CONCRETE	12.000	CY
0350	511(B)2310	EPOXY COATED REINFORCING STEEL	165,650.000	LB
0360	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0370	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	31,806.000	SY
0380	517 9110	ELASTOMERIC COATING	6,068.000	SF
0390	518(B)0310	EXPANSION JOINT SYSTEM	580.000	LF
0400	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	550.000	LF
0410	520(C)1400	EPOXY RESIN, ABOVE WATER	48.000	GAL
0420	521(A)2200	PNEUMATICALLY PLACED MORTAR	182.000	SY
0430	523(A)3200	SEALER CRACK PREPARATION	4,011.000	LF
0440	523(B)3300	SEALER RESIN	47.000	GAL
0450	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	3,040.000	SF
0460	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	74.000	SY
0470	540 8120	(PL)REPAIR BRIDGE ITEM (TYPE A)	4.000	EA
0480	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal: 260303 **Let Date:** November 19, 2026 **Call Order:** 044
J/P Num: 36893(04) **Proj. Num:** IN-MC-78
38909(04) IN-MC-80
Counties: MCINTOSH, PITTSBURG
Description: BRIDGE REHABILITATION
INDIAN NATION TURNPIKE/SH-375 (OTA ACCESS): OVER SOUTH CANADIAN RIVER AND OVERFLOW, 8.6 MILES SOUTH OF THE SH-9 INTERCHANGE NEAR VERNON.
PROJECT LENGTH = 0.894 MILES

	Line #		Item Description	Quantity	Unit
0009	ROADWAY - IN-MC-80				
	0490	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
	0500	202(A)2200	UNCLASSIFIED EXCAVATION	400.000	CY
	0510	202(D)2500	UNCLASSIFIED BORROW	2,150.000	CY
	0520	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
	0530	221(B)2300	TEMPORARY SILT FENCE	4,701.000	LF
	0540	230(A)7200	SOLID SLAB SODDING	6,229.000	SY
	0550	233(A)0200	VEGETATIVE MULCHING	1.200	AC
	0560	241 3100	MOWING	2.400	AC
	0570	307(K)4200	STABILIZED SUBGRADE	7,285.000	SY
	0580	310(B)5300	SUBGRADE, METHOD B	476.000	SY
	0590	407(B)7300	TACK COAT	728.000	GAL
	0600	408 8100	PRIME COAT	3,873.000	GAL
	0610	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,921.000	TON
	0620	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	1,072.000	TON
	0630	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	4,323.000	LF
	0640	413(C)4400	RUMBLE STRIP-METHOD PCC-CON	571.000	LF
	0650	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	476.000	SY
	0660	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	1,521.000	SY
	0670	414(G)5800	P.C. CONCRETE FOR PAVEMENT	447.000	CY
	0680	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	1,996.000	SY
	0690	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	43,230.000	SY
	0700	619(B)6396	REMOVAL OF GUARDRAIL	4,175.000	LF
	0710	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	3,975.000	LF
	0720	623(G)1820	GUARDRAIL END TREATMENT (31")	1.000	EA
	0730	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	3.000	EA
	0740	625(B)4300	REMOVE AND RECONSTRUCT FENCE	765.000	LF
	0750	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	52.000	EA

Proposal: 260303 **Let Date:** November 19, 2026 **Call Order:** 044
J/P Num: 36893(04) **Proj. Num:** IN-MC-78
38909(04) IN-MC-80
Counties: MCINTOSH, PITTSBURG
Description: BRIDGE REHABILITATION
INDIAN NATION TURNPIKE/SH-375 (OTA ACCESS): OVER SOUTH CANADIAN RIVER AND OVERFLOW, 8.6 MILES SOUTH OF THE SH-9 INTERCHANGE NEAR VERNON.
PROJECT LENGTH = 0.894 MILES

Line #		Item Description	Quantity	Unit
0010	BRIDGE - IN-MC-80			
0760	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	120.000	CY
0770	501(G)1800	CLSM BACKFILL	240.000	CY
0780	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	3,983.350	LF
0790	504(A)5200	APPROACH SLAB	358.400	SY
0800	504(B)5300	SAW-CUT GROOVING	3,500.000	SY
0810	504(E)5520	42" F-SHAPED PARAPET	886.000	LF
0820	506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	4,350.000	LB
0830	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	60.000	EA
0840	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	30.000	EA
0850	509(A)0210	CLASS AA CONCRETE	908.600	CY
0860	509(B)0320	CLASS A CONCRETE	20.000	CY
0870	509(D)0510	CLASS C CONCRETE	12.000	CY
0880	511(B)2310	EPOXY COATED REINFORCING STEEL	173,238.000	LB
0890	513(B)4300	CLASS B BRIDGE DECK REPAIR	35.000	SY
0900	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	8,937.000	SY
0910	517 9110	ELASTOMERIC COATING	1,984.000	SF
0920	518(B)0310	EXPANSION JOINT SYSTEM	144.000	LF
0930	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	184.000	LF
0940	520(C)1400	EPOXY RESIN, ABOVE WATER	17.500	GAL
0950	521(A)2200	PNEUMATICALLY PLACED MORTAR	98.000	SY
0960	523(A)3200	SEALER CRACK PREPARATION	1,015.000	LF
0970	523(B)3300	SEALER RESIN	12.000	GAL
0980	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	35.000	SF
0990	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	258.000	SY
1000	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0011	TRAFFIC CONTROL - IN-MC-80			
1010	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	45,180.000	LF
1020	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	45,180.000	LF
1030	871(B)2300	CONST.ZONE IMPACT ATTEN.	2,210.000	SD
1040	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	9,850.000	LF
1050	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	9,850.000	LF
1060	880(A)6220	ARROW DISPLAY(TYPE C)	1,860.000	SD
1070	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,150.000	SD
1080	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	6,880.000	SD
1090	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	7,200.000	SD
1100	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	8,820.000	SD
1110	880(E)6600	WARNING LIGHTS(TYPE A)	16,000.000	SD
1120	880(F)6700	DRUMS	51,824.000	SD
1130	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	480.000	HOUR
1140	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	640.000	SD
0012	TRAFFIC SIGNING AND STRIPING - IN-MC-80			
1150	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	61,224.000	LF

Proposal: 260303 **Let Date:** November 19, 2026 **Call Order:** 044
J/P Num: 36893(04) **Proj. Num:** IN-MC-78
38909(04) IN-MC-80
Counties: MCINTOSH, PITTSBURG
Description: BRIDGE REHABILITATION
INDIAN NATION TURNPIKE/SH-375 (OTA ACCESS): OVER SOUTH CANADIAN RIVER AND OVERFLOW, 8.6 MILES SOUTH OF THE SH-9 INTERCHANGE NEAR VERNON.
PROJECT LENGTH = 0.894 MILES

	Line #		Item Description	Quantity	Unit
0013	TRAFFIC CABLE BARRIER - IN-MC-80				
	1160	509(A)0200	CLASS AA CONCRETE	51.230	CY
	1170	619(B)6432	REMOVAL OF CABLE BARRIER	6,164.000	LF
	1180	628(B)7300	HIGH-TENSION CABLE BARRIER(TL-4)	6,164.000	LF
	1190	628(C)7400	END ANCHORS	4.000	EA
0014	STAKING - IN-MC-80				
	1200	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0015	CONSTRUCTION - IN-MC-80				
	1210	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	1220	641 2100	MOBILIZATION	1.000	LSUM