Proposal:260305 **Let Date:**November 19, 2026 **Call Order:**048
J/P Num:38910(04) **Proj. Num:**MU-MC-56
Counties:WAGONER
Description:BRIDGE REHABILITATION
OTA ACCESS MUSKOGEE TURNPIKE (SH-351)/ COUNTY ROAD (E0770): OVER MUSKOGEE TURNPIKE, 7.27 MILES NORTHWEST OF THE US-69 INTERCHANGE NEAR MUSKOGEE.
PROJECT LENGTH = 1.657 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	34,484.000	CY
0030	202(C)2400	ROCK EXCAVATION	1,000.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	4,963.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	973.000	LF
0070	221(F)2710	TEMPORARY ROCK FILTER DAM TYPE 2	29.000	CY
0080	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	4.000	EA
0090	230(A)7200	SOLID SLAB SODDING	44,635.000	SY
0100	233(A)0200	VEGETATIVE MULCHING	9.220	AC
0110	241 3100	MOWING	18.440	AC
0120	242 4101	STABILIZED CONSTRUCTION EXIT	1.000	EA
0130	303(A)1200	AGGREGATE BASE TYPE A	5,299.000	CY
0140	307(K)4200	STABILIZED SUBGRADE	20,818.000	SY
0150	325 0100	SEPARATOR FABRIC	14,280.000	SY
0160	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	3,749.000	TON
0170	407(B)7300	TACK COAT	997.000	GAL
0180	408 8100	PRIME COAT	444.000	GAL
0190	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,982.000	TON
0200	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	648.000	TON
0210	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	5,330.000	SY
0220	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	6,580.000	SY
0230	414(G)5800	P.C. CONCRETE FOR PAVEMENT	3,170.000	CY
0240	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	34.000	CY
0250	509(B)0300	CLASS A CONCRETE	82.000	CY
0260	509(D)0500	CLASS C CONCRETE	550.000	CY
0270	511(A)2200	REINFORCING STEEL	11,232.000	LB
0280	601(A)1100	TYPE I PLAIN RIPRAP	88.000	TON
0290	611(G)7978	INLET GPI TYPE 2 (DES. 12)	1.000	EA
0300	611(G)7982	INLET GPI TYPE 2 (DES. 13)	1.000	EA
0310	611(G)9039	PRECAST INLET (CDI RCP DES. 1B)	1.000	EA
0320	611(G)9040	PRECAST INLET (CDI RCP DES. 2)	1.000	EA
0330	613(A)5208	18" R.C.PIPE CLASS III	40.000	LF
0340	613(A)5216	24" R.C.PIPE CLASS III	174.000	LF
0350	613(A)5220	30" R.C.PIPE CLASS III	234.000	LF
0360	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0370	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0380	613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	3.000	EA
0390	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0400	619(B)6352	REMOVAL OF FENCE	1,044.000	LF
0410	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	3,683.000	SY
0420	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	4,127.000	SY
0430	619(B)6396	REMOVAL OF GUARDRAIL	1,929.000	LF
0440	619(C)6600	SAWING PAVEMENT	2,595.000	LF
0450	624(A)3200	FENCE-STYLE WWF	436.000	LF
0460	627(A)6200	CONCRETE LONGITUDINAL BARRIER, DESIGN 1	537.000	LF

Proposal:260305 **Let Date:**November 19, 2026 **Call Order:**048
J/P Num:38910(04) **Proj. Num:**MU-MC-56
Counties:WAGONER
Description:BRIDGE REHABILITATION
OTA ACCESS MUSKOGEE TURNPIKE (SH-351)/ COUNTY ROAD (E0770): OVER MUSKOGEE TURNPIKE, 7.27 MILES NORTHWEST OF THE US-69 INTERCHANGE NEAR MUSKOGEE.
PROJECT LENGTH = 1.657 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE			
0470	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	80.000	CY
0480	501(G)1800	CLSM BACKFILL	134.000	CY
0490	504(A)5200	APPROACH SLAB	187.400	SY
0500	504(B)5300	SAW-CUT GROOVING	1,522.400	SY
0510	504(D)5420	CONCRETE RAIL (TR4)	681.000	LF
0520	506(A)7200	STRUCTURAL STEEL	317,980.000	LB
0530	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	8.000	EA
0540	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	24.000	EA
0550	507(C)8400	ELASTOMERIC BEARING PADS	24.000	EA
0560	509(A)0210	CLASS AA CONCRETE	349.000	CY
0570	509(B)0320	CLASS A CONCRETE	261.200	CY
0580	509(D)0510	CLASS C CONCRETE	10.000	CY
0590	510(C)1450	SLOPE WALL (5")	548.000	SY
0600	511(B)2310	EPOXY COATED REINFORCING STEEL	129,270.000	LB
0610	514(A)5210	PILES, FURNISHED (HP 10X42)	364.000	LF
0620	514(B)5310	PILES, DRIVEN (HP 10X42)	364.000	LF
0630	514(K)6200	(PL)PILOT HOLES	210.000	LF
0640	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0650	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	878.000	SY
0660	516(A)8250	DRILLED SHAFTS 72" DIAMETER	207.000	LF
0670	516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
0680	523(A)3200	SEALER CRACK PREPARATION	244.500	LF
0690	523(B)3300	SEALER RESIN	2.700	GAL
0700	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	182.000	LF
0710	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	100.000	LF
0720	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA
0730	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260305 **Let Date:**November 19, 2026 **Call Order:**048
J/P Num:38910(04) **Proj. Num:**MU-MC-56
Counties:WAGONER
Description:BRIDGE REHABILITATION
OTA ACCESS MUSKOGEE TURNPIKE (SH-351)/ COUNTY ROAD (E0770): OVER MUSKOGEE TURNPIKE, 7.27 MILES NORTHWEST OF THE US-69 INTERCHANGE NEAR MUSKOGEE.
PROJECT LENGTH = 1.657 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC SIGNING AND STRIPING			
0740	804(A)2200	STRUCTURAL CONCRETE	13.200	CY
0750	804(B)2300	REINFORCING STEEL	2,668.000	LB
0760	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	16.000	EA
0770	850(A)1200	SHEET ALUMINUM SIGNS	418.000	SF
0780	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	270.000	SF
0790	851(A)2205	6"@15 GALV.STL.WD.FLANGE BM.POST	37.000	LF
0800	851(A)2235	10"@45 GALV.STL.WD.FLANGE BM.POST	126.000	LF
0810	851(B)2310	2 1/2"@5.79 GALV.STL.PIPE POST	135.000	LF
0820	851(B)2320	3 1/2"@9.11 GALV.STL.PIPE POST	180.000	LF
0830	851(C)2420	2 1/4" SQUARE TUBE POST	126.000	LF
0840	851(C)2430	2 1/2" SQUARE TUBE POST	120.000	LF
0850	853 5130	DELINEATORS(TYPE 1, CODE 1, FLEXIBLE)	38.000	EA
0860	853 5135	DELINEATORS(TYPE 1, CODE 2, FLEXIBLE)	18.000	EA
0870	853 5155	DELINEATORS(TYPE 2, CODE 3, FLEXIBLE)	8.000	EA
0880	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	33,338.000	LF
0890	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	957.000	LF
0900	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	113.000	LF
0910	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	5.000	EA
0920	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	60.000	EA
0930	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	49.000	EA
0940	871(A)2200	IMPACT ATTENUATOR	6.000	EA
0004	TRAFFIC CONTROL			
0950	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	32,350.000	LF
0960	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	40,438.000	LF
0970	871(B)2300	CONST.ZONE IMPACT ATTEN.	420.000	SD
0980	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	4,125.000	LF
0990	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	3,070.000	LF
1000	880(A)6220	ARROW DISPLAY(TYPE C)	840.000	SD
1010	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	28,170.000	SD
1020	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	12,900.000	SD
1030	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,690.000	SD
1040	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	5,700.000	SD
1050	880(E)6607	WARNING LIGHTS(TYPE B)	16,200.000	SD
1060	880(F)6700	DRUMS	16,740.000	SD
1070	880(G)6805	CHANNELIZER CONES	23,010.000	SD
1080	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	1,200.000	HOUR
1090	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	600.000	SD

Proposal:260305 **Let Date:**November 19, 2026 **Call Order:**048
J/P Num:38910(04) **Proj. Num:**MU-MC-56
Counties:WAGONER
Description:BRIDGE REHABILITATION
OTA ACCESS MUSKOGEE TURNPIKE (SH-351)/ COUNTY ROAD (E0770): OVER MUSKOGEE TURNPIKE, 7.27 MILES NORTHWEST OF THE US-69 INTERCHANGE NEAR MUSKOGEE.
PROJECT LENGTH = 1.657 MILES

Line #		Item Description	Quantity	Unit
0005	TOLLING			
1100	506(A)7200	STRUCTURAL STEEL	1,300.000	LB
1110	516(A)8230	DRILLED SHAFTS 48" DIAMETER	71.000	LF
1120	516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
1130	610(A)5200	4" CONCRETE SIDEWALK	112.000	SY
1140	648 6110	ELECTRIC SERVICE AND SERVICE CONNECTION	1.000	LSUM
1150	650(C)8310	ELECTRICAL EQUIPMENT	1.000	LSUM
1160	802(B)0308	1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	185.000	LF
1170	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	75.000	LF
1180	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	335.000	LF
1190	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	905.000	LF
1200	803(A)1220	PULL BOX(SIZE II)	12.000	EA
1210	804(A)2200	STRUCTURAL CONCRETE	1.460	CY
1220	811 9165	3/C NO.3 ELECT.COND.	1,240.000	LF
1230	824(C)7400	(SP)CABINET	2.000	EA
1240	852(B)3340	GALVANIZED STEEL OVERHEAD TOLL GANTRY (CANTILEVER	2.000	EA
0006	STAKING			
1250	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION			
1260	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1270	641 2110	MOBILIZATION	1.000	LSUM