Proposal: 260306 **Let Date:** November 19, 2026 **Call Order:** 400
J/P Num: 38846(04) **Proj. Num:** CIRB-206D(076)RB
Counties: BLAINE
Description: GRADE, DRAIN AND SURFACE
COUNTY ROADS (NS 2520/EW 0940): FROM 10.0 MILES WEST OF THE US-270 JUNCTION, EXTEND WEST AND SOUTH NEAR AMERICAN HORSE LAKE.

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(H)2900	EARTHWORK	1.000	LSUM
0020	221(B)2300	TEMPORARY SILT FENCE	246.000	LF
0030	221(E)2600	TEMPORARY SILT DIKE	28.000	LF
0040	230(A)7200	SOLID SLAB SODDING	220.000	SY
0050	303(A)1200	AGGREGATE BASE TYPE A	32.000	CY
0060	326(B)1300	GEOGRID REINFORCEMENT	139.000	SY
0070	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	54.000	TON
0080	407(B)7300	TACK COAT	11.000	GAL
0090	408 8100	PRIME COAT	45.000	GAL
0100	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	33.000	TON
0110	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	16.000	TON
0120	509(D)0500	CLASS C CONCRETE	2.300	CY
0130	601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	733.000	TON
0140	613(A)5280	42" R.C.PIPE CLASS IV	150.000	LF
0150	613(B)5508	18" CORR. GALV. STEEL PIPE	80.000	LF
0160	613(M)6932	TYPE DD3 CULVERT END TREATMENT	2.000	EA
0170	613(M)6960	TYPE A4 CULVERT END TREATMENT	2.000	EA
0180	619(B)6352	REMOVAL OF FENCE	774.000	LF
0190	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	424.000	LF
0200	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	650.000	LF
0002	TRAFFIC			
0210	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	117.000	LF
0220	880(J)7100	(SP) CONSTRUCTION TRAFFIC CONTROL	30.000	SD
0003	STAKING			
0230	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004	CONSTRUCTION			
0240	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0250	641 2110	MOBILIZATION	1.000	LSUM