Proposal:260307 **Let Date:**January 21, 2027 **Call Order:**620
J/P Num:36951(04) **Proj. Num:**STPG-214B(199)AG
Counties:CLEVELAND
Description:TRAFFIC SIGNALS
CITY STREET (36TH AVENUE NW): AT THE INTERSECTION OF BART CONNER DRIVE IN THE CITY OF NORMAN.
PROJECT LENGTH = 0.100 MILES

Line #		Item Description	Quantity	Unit
0001	TRAFFIC			
0010	230(A)7200	SOLID SLAB SODDING	218.000	SY
0020	610(A)5200	4" CONCRETE SIDEWALK	24.000	SY
0030	610(I)6000	TACTILE WARNING DEVICE-NEW	40.000	SF
0040	616(P)4128	4" HDPE PIPE	125.000	LF
0050	616(P)4132	4" HDPE PIPE (BORED)	185.000	LF
0060	802(C)0430	2" HIGH DENSITY PE PIPE - TRENCHED	95.000	LF
0070	802(C)0440	3" HIGH DENSITY PE PIPE - TRENCHED	72.000	LF
0080	803(A)1200	PULL BOX	1.000	EA
0090	803(A)1220	PULL BOX(SIZE II)	3.000	EA
0100	804(A)2200	STRUCTURAL CONCRETE	17.350	CY
0110	804(B)2300	REINFORCING STEEL	2,495.000	LB
0120	806(A)4284	32'MH POLE 30'TS & 15'LMA(G.STL.)	1.000	EA
0130	806(A)4292	32'MH POLE 40'TS & 15'LMA(G.STL.)	1.000	EA
0140	806(A)4296	32'MH POLE 45'TS & 15'LMA(G.STL.)	1.000	EA
0150	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	3.000	EA
0160	809(A)7200	ROADWAY LUMINAIRE	3.000	EA
0170	810(A)8200	SERVICE POLE	1.000	EA
0180	811 9120	1/C NO.6 ELECT.COND.	150.000	LF
0190	811 9130	1/C NO.10 ELECT.COND.	782.000	LF
0200	818(A)4200	(SP)FIBER OPTIC CABLE, 12 SMF	137.000	LF
0210	818(B)4300	(SP)FIBER OPTIC PATCH PANEL, 12 PORT	1.000	EA
0220	818(C)4400	(SP)FIBER OPTIC CABLE SPLICE	12.000	EA
0230	818(D)4500	(SP)FIBER OPTIC CABLE TERMINATION	12.000	EA
0240	824(C)7400	(SP)CABINET	1.000	EA
0250	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	1.000	EA
0260	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
0270	830 2100	PEDESTRIAN PUSH BUTTON	6.000	EA
0280	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	6.000	EA
0290	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	6.000	EA
0300	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	1.000	EA
0310	833 5100	BACKPLATE	7.000	EA
0320	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,001.000	LF
0330	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	238.000	LF
0340	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	512.000	LF
0350	834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	49.000	LF
0360	840(B)0300	E.P.S. OPTICAL DETECTOR	1.000	EA
0370	840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	65.000	LF
0380	840(D)0510	E.P.S. 4 CHANNEL PHASE SELECTOR	1.000	EA
0390	850(A)1200	SHEET ALUMINUM SIGNS	6.000	SF
0400	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	62.000	SF
0410	855(A)7201	(SP) TRAFFIC STRIPE(PLASTIC)(4" WIDE)	200.000	LF
0420	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	1,908.000	LF
0430	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	520.000	LF
0440	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	110.000	LF
0450	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	18.000	LF
0460	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	335.000	LF

Proposal: 260307 **Let Date:** January 21, 2027 **Call Order:** 620
J/P Num: 36951(04) **Proj. Num:** STPG-214B(199)AG
Counties: CLEVELAND
Description: TRAFFIC SIGNALS
CITY STREET (36TH AVENUE NW): AT THE INTERSECTION OF BART CONNER DRIVE IN THE CITY OF NORMAN.
PROJECT LENGTH = 0.100 MILES

Line #		Item Description	Quantity	Unit
0001	TRAFFIC			
0470	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	2.000	EA
0480	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	2,150.000	LF
0490	857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	3.000	EA
0002	TEMPORARY TRAFFIC			
0500	880(B)6305	CONSTRUCTION SIGNS 0 TO 6.25 SF	3.000	EA
0510	880(B)6315	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	7.000	EA
0520	880(F)6705	DRUMS	45.000	EA
0003	STAKING			
0530	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004	CONSTRUCTION			
0540	641 2110	MOBILIZATION	1.000	LSUM