Proposal: 260309 **Let Date:** November 19, 2026 **Call Order:** 420
J/P Num: 36364(04) **Proj. Num:** SBR-232B(079)SB
Counties: HUGHES
Description: BRIDGE REHABILITATION
US-75: OVER CANADIAN RIVER AND COUNTY ROAD
(E -141), 0.75 MILES NORTH OF THE US-270 JUNCTION NEAR CALVIN.
PROJECT LENGTH = 0.256 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	221(B)2300	TEMPORARY SILT FENCE	100.000	LF
0020	230(A)7200	SOLID SLAB SODDING	1,000.000	SY
0030	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0040	623(I)2040	GUARDRAIL BRIDGE CONN (D-BF RETROFIT)	4.000	EA
0002	BRIDGE			
0050	504(E)5500	CONCRETE PARAPET	120.000	LF
0060	509 0100	SPECIAL CONCRETE FINISH	1,810.000	SY
0070	509(A)0210	CLASS AA CONCRETE	11.200	CY
0080	509(D)0510	CLASS C CONCRETE	10.000	CY
0090	511(B)2310	EPOXY COATED REINFORCING STEEL	1,320.000	LB
0100	512 3100	CLEANING BRIDGE SURFACES	100.000	SY
0110	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0120	517 9110	ELASTOMERIC COATING	5,600.000	SF
0130	518(B)0300	SEALED EXPANSION JOINTS	208.000	LF
0140	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	800.000	LF
0150	520(C)1400	EPOXY RESIN, ABOVE WATER	12.000	GAL
0160	521(A)2200	PNEUMATICALLY PLACED MORTAR	40.000	SY
0170	523(C)3400	DECK AREA SEALED (FLOODCOATS)	6,907.000	SY
0180	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	150.000	SF
0190	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	60.000	SY
0200	540 8104	(PL)REPAIR BRIDGE ITEMS	13.000	EA
0210	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	590.000	TON
0220	619(B)6312	REMOVAL OF BRIDGE ITEM (TYPE A)	1.000	LSUM
0230	619(B)6320	REMOVAL OF BRIDGE ITEM (TYPE B)	1.000	LSUM
0240	619(B)6328	REMOVAL OF BRIDGE ITEM (TYPE C)	1.000	LSUM
0003	TRAFFIC STRIPING			
0250	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	15,656.000	LF

Proposal: 260309 **Let Date:** November 19, 2026 **Call Order:** 420
J/P Num: 36364(04) **Proj. Num:** SBR-232B(079)SB
Counties: HUGHES
Description: BRIDGE REHABILITATION
US-75: OVER CANADIAN RIVER AND COUNTY ROAD
(E -141), 0.75 MILES NORTH OF THE US-270 JUNCTION NEAR CALVIN.
PROJECT LENGTH = 0.256 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL			
0260	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	125.000	SD
0270	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	10,347.000	LF
0280	857(F)9740	PAVEMENT MARKING REMOVAL (HYDROBLASTING)	22,459.000	LF
0290	858(A)0216	PAVE.MARKERS CLASS A TYPE 2-A	2,500.000	EA
0300	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	910.000	EA
0310	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	500.000	SD
0320	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,253.000	SD
0330	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,099.000	SD
0340	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,125.000	SD
0350	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,141.000	SD
0360	880(E)6607	WARNING LIGHTS(TYPE B)	6,907.000	SD
0370	880(E)6616	WARNING LIGHTS(TYPE D)	1,950.000	SD
0380	880(F)6700	DRUMS	2,500.000	SD
0390	880(G)6800	TUBE CHANNELIZERS	5,980.000	SD
0395	880(K)7200	SURVEILLANCE TRAFFIC CONTROL	125.000	SD
0400	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	278.000	SD
0005	CONSTRUCTION			
0410	641 2100	MOBILIZATION	1.000	LSUM