Proposal: 260316 **Let Date:** November 19, 2026 **Call Order:** 460
J/P Num: 31177(04) **Proj. Num:** STP-274C(046)CI
Counties: WASHINGTON
Description: BRIDGE AND APPROACHES
COUNTY ROAD (N 4000 ROAD): OVER SAUNDERS CREEK,
2 MILES EAST OF THE US-75 JUNCTION IN THE TOWN OF VERA.
PROJECT LENGTH = 0.199 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	917.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	3,840.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	2,036.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	100.000	LF
0070	230(A)7200	SOLID SLAB SODDING	8,012.000	SY
0080	303(A)1200	AGGREGATE BASE TYPE A	864.000	CY
0090	310(B)5300	SUBGRADE, METHOD B	3,624.000	SY
0100	325 0100	SEPARATOR FABRIC	3,624.000	SY
0110	407(B)7300	TACK COAT	227.000	GAL
0120	408 8100	PRIME COAT	696.000	GAL
0130	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	683.000	TON
0140	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	338.000	TON
0150	601(A)1100	TYPE I PLAIN RIPRAP	128.000	TON
0160	611(G)0354	INLET (SMD-TYPE 2)	2.000	EA
0170	613(A)5208	18" R.C.PIPE CLASS III	121.000	LF
0180	613(M)6960	TYPE A4 CULVERT END TREATMENT	1.000	EA
0190	613(T)7800	STANDARD BEDDING MATERIAL, CLASS C	68.000	CY
0200	613(V)8000	TRENCH EXCAVATION	68.000	CY
0210	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0220	619(B)6376	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	2,173.000	SY
0230	619(C)6600	SAWING PAVEMENT	79.000	LF
0240	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	300.000	LF
0250	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0260	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
0270	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	350.000	LF
0280	624(D)3500	GATE, GALVANIZED STEEL	1.000	EA
0290	626(A)5200	MONUMENTS	1.000	EA

Proposal:260316 **Let Date:**November 19, 2026 **Call Order:**460
J/P Num:31177(04) **Proj. Num:**STP-274C(046)CI
Counties:WASHINGTON
Description:BRIDGE AND APPROACHES
COUNTY ROAD (N 4000 ROAD): OVER SAUNDERS CREEK,
2 MILES EAST OF THE US-75 JUNCTION IN THE TOWN OF VERA.
PROJECT LENGTH = 0.199 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE			
0300	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	190.000	CY
0310	501(D)1500	UNCLASSIFIED BACKFILL	300.000	CY
0320	501(G)1800	CLSM BACKFILL	88.000	CY
0330	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	299.000	LF
0340	504(B)5300	SAW-CUT GROOVING	249.800	SY
0350	504(D)5410	CONCRETE RAIL (TR3)	266.400	LF
0360	506(A)7200	STRUCTURAL STEEL	290.000	LB
0370	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	3.000	EA
0380	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	3.000	EA
0390	509(A)0210	CLASS AA CONCRETE	79.000	CY
0400	509(B)0320	CLASS A CONCRETE	70.000	CY
0410	511(A)2210	REINFORCING STEEL	10,020.000	LB
0420	511(B)2310	EPOXY COATED REINFORCING STEEL	18,340.000	LB
0430	514(A)5210	PILES, FURNISHED (HP 10X42)	92.000	LF
0440	514(A)5220	PILES, FURNISHED (HP 12X53)	252.000	LF
0450	514(B)5310	PILES, DRIVEN (HP 10X42)	92.000	LF
0460	514(B)5320	PILES, DRIVEN (HP 12X53)	252.000	LF
0470	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0480	517 9110	ELASTOMERIC COATING	382.700	SF
0490	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	2,599.000	TON
0500	601(I)1700	FILTER FABRIC (RIPRAP)	2,079.000	SY
0510	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	52.000	LF
0520	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	80.000	LF
0530	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	TRAFFIC			
0540	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0550	836 7100	REGULATORY OR WARNING SIGN ASSEMBLY	2.000	EA
0560	850(A)1200	SHEET ALUMINUM SIGNS	40.910	SF
0570	851(C)2415	2" SQUARE TUBE POST	50.000	LF
0580	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	4,178.000	LF
0590	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	24.000	LF
0004	TRAFFIC TEMPORARY			
0600	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,080.000	SD
0610	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	360.000	SD
0620	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	720.000	SD
0630	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,080.000	SD
0640	880(E)6600	WARNING LIGHTS(TYPE A)	2,160.000	SD
0005	STAKING			
0650	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0660	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0670	641 2100	MOBILIZATION	1.000	LSUM