Proposal:270003 **Let Date:**January 14, 2027 **Call Order:**506
J/P Num:33762(04) **Proj. Num:**NHPPI-4000-(210)FP
Counties:CADDO, CANADIAN
Description:RESURFACE (ASPHALT AND UTBWC)
I-40: FROM 0.6 MILES EAST OF US-281, EXTEND EAST NEAR HINTON.
PROJECT LENGTH = 2.029

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	804.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	2,440.000	CY
0030	221(B)2300	TEMPORARY SILT FENCE	42,856.000	LF
0040	221(E)2600	TEMPORARY SILT DIKE	294.000	LF
0050	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	7.000	EA
0060	230(A)7200	SOLID SLAB SODDING	64,284.000	SY
0070	233(A)0200	VEGETATIVE MULCHING	13.290	AC
0080	241 3100	MOWING	26.570	AC
0090	404(A)4200	ULTRA-THIN BONDED WEARING COURSE, TYPE A	2,951.000	TON
0100	407(B)7300	TACK COAT	2,827.000	GAL
0110	407(C)7400	(SP) POLYMER MOD. CATIONIC RAPID SET - 1S	18,095.000	GAL
0120	408 8100	PRIME COAT	4,857.000	GAL
0130	411(L)2432	BMD, TYPE B4 (PG 76-28 OK)	15,868.000	TON
0140	412 3100	COLD MILLING PAVEMENT	90,474.000	SY
0150	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	42,856.000	LF
0160	509(A)0200	CLASS AA CONCRETE	113.000	CY
0170	509(D)0500	CLASS C CONCRETE	10.000	CY
0180	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	13,876.000	SY
0190	619(B)6396	REMOVAL OF GUARDRAIL	4,336.000	LF
0200	619(B)6432	REMOVAL OF CABLE BARRIER	11,238.000	LF
0210	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	4,650.000	LF
0220	623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	8.000	EA
0230	623(G)1820	GUARDRAIL END TREATMENT (31")	8.000	EA
0240	628 7100	INSTALLATION OF CABLE BARRIER SYSTEM	11,238.000	LF
0250	628(C)7400	END ANCHORS	3.000	EA
0260	628(E)7600	CABLE BARRIER TENSION METER	1.000	EA
0270	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	118.000	EA
0002	TRAFFIC SIGNING AND STRIPING			
0280	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	12.000	EA
0290	850(A)1200	SHEET ALUMINUM SIGNS	156.000	SF
0300	851(C)2420	2 1/4" SQUARE TUBE POST	216.000	LF
0310	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	51,500.000	LF
0320	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	10,000.000	LF

Proposal:270003 **Let Date:**January 14, 2027 **Call Order:**506
J/P Num:33762(04) **Proj. Num:**NHPPI-4000-(210)FP
Counties:CADDO, CANADIAN
Description:RESURFACE (ASPHALT AND UTBWC)
I-40: FROM 0.6 MILES EAST OF US-281, EXTEND EAST NEAR HINTON.
PROJECT LENGTH = 2.029

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0330	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	73,000.000	LF
0340	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	14,600.000	EA
0350	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	1,000.000	EA
0360	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	1,000.000	EA
0370	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	175.000	SD
0380	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,040.000	SD
0390	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,380.000	SD
0400	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,380.000	SD
0410	880(B)6340	VARIABLE SPEED LIMIT SIGN	8,840.000	SD
0420	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	510.000	SD
0430	880(E)6607	WARNING LIGHTS(TYPE B)	680.000	SD
0440	880(E)6616	WARNING LIGHTS(TYPE D)	5,610.000	SD
0450	880(F)6700	DRUMS	5,610.000	SD
0460	880(G)6805	CHANNELIZER CONES	36,040.000	SD
0470	880(K)7200	SURVEILLANCE TRAFFIC CONTROL	85.000	SD
0480	882 8100	(SP)SMART WORK ZONE SYSTEM	85.000	SD
0490	882 8105	(SP)SMART WK. ZONE SYS.-PORT.CHNG.MSG.SN	340.000	SD
0500	882 8110	(SP)SMART WK. ZONE SYS.-PORT.TRAF.SENSOR	1,020.000	SD
0510	882 8115	(SP)SMART WK ZONE SYS-PAN-TILT-ZOOM CMRA	170.000	SD
0520	882 8120	(SP)SMART WK. ZONE SYS.-WEBSITE SYSTEM	85.000	SD
0530	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	594.000	SD
0004	STAKING			
0540	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0550	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0560	641 2110	MOBILIZATION	1.000	LSUM