Proposal:270042 **Let Date:**January 21, 2027 **Call Order:**665
J/P Num:38369(04) **Proj. Num:**SBR-248C(066)SB
Counties:MARSHALL
Description:BRIDGE REHABILITATION
SH-32: OVER BRIAR CREEK, 1.8 MILES EAST
OF THE US-377 JUNCTION NEAR KINGSTON.
PROJECT LENGTH = 0.078 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	771.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	1,208.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	945.000	LF
0060	230(A)7200	SOLID SLAB SODDING	4,000.000	SY
0070	242 4101	STABILIZED CONSTRUCTION EXIT	1.000	EA
0080	303(A)1200	AGGREGATE BASE TYPE A	106.000	CY
0090	325 0100	SEPARATOR FABRIC	411.000	SY
0100	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	65.000	TON
0110	407(B)7300	TACK COAT	142.000	GAL
0120	408 8100	PRIME COAT	129.000	GAL
0130	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	132.000	TON
0140	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	115.000	TON
0150	412 3100	COLD MILLING PAVEMENT	588.000	SY
0160	601(A)1100	TYPE I PLAIN RIPRAP	220.000	TON
0170	602(C)2410	FILTER FABRIC	270.000	SY
0180	613(B)5508	18" CORR. GALV. STEEL PIPE	30.000	LF
0190	613(EE)6109	36" POLYPROPYLENE PIPE	300.000	LF
0200	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0210	619(B)6352	REMOVAL OF FENCE	100.000	LF
0220	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	126.000	SY
0230	619(B)6386	REMOVAL OF GRAVEL DRIVEWAY	152.000	SY
0240	619(B)6396	REMOVAL OF GUARDRAIL	200.000	LF
0250	619(C)6600	SAWING PAVEMENT	537.000	LF
0260	623 1100	(PL)GUARDRAIL CURBING	2.000	EA
0270	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	200.000	LF
0280	623(G)1820	GUARDRAIL END TREATMENT (31")	2.000	EA
0290	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0300	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	82.000	LF
0310	624(D)3500	GATE, GALVANIZED STEEL	1.000	EA
0320	629(D)7500	REMOVE AND RESET MAILBOX	2.000	EA

Proposal:270042 **Let Date:**January 21, 2027 **Call Order:**665
J/P Num:38369(04) **Proj. Num:**SBR-248C(066)SB
Counties:MARSHALL
Description:BRIDGE REHABILITATION
SH-32: OVER BRIAR CREEK, 1.8 MILES EAST
OF THE US-377 JUNCTION NEAR KINGSTON.
PROJECT LENGTH = 0.078 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE 'A'			
0330	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	120.000	CY
0340	501(G)1800	CLSM BACKFILL	185.000	CY
0350	504(A)5200	APPROACH SLAB	255.000	SY
0360	504(B)5300	SAW-CUT GROOVING	786.000	SY
0370	504(D)5420	CONCRETE RAIL (TR4)	392.300	LF
0380	506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	133,820.000	LB
0390	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	18.000	EA
0400	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	18.000	EA
0410	509(A)0210	CLASS AA CONCRETE	135.100	CY
0420	509(B)0320	CLASS A CONCRETE	137.300	CY
0430	509(D)0510	CLASS C CONCRETE	10.000	CY
0440	511(A)2210	REINFORCING STEEL	1,060.000	LB
0450	511(B)2310	EPOXY COATED REINFORCING STEEL	61,340.000	LB
0460	514(A)5220	PILES, FURNISHED (HP 12X53)	888.000	LF
0470	514(B)5320	PILES, DRIVEN (HP 12X53)	888.000	LF
0480	514(K)6200	(PL)PILOT HOLES	888.000	LF
0490	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	752.000	SY
0500	516(A)8225	DRILLED SHAFTS 42" DIAMETER	126.000	LF
0510	516(C)8400	CROSSHOLE SONIC LOGGING	4.000	EA
0520	517 9110	ELASTOMERIC COATING	993.000	SF
0530	518(B)0300	SEALED EXPANSION JOINTS	79.000	LF
0540	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	116.000	LF
0550	520(C)1400	EPOXY RESIN, ABOVE WATER	7.000	GAL
0560	521(A)2200	PNEUMATICALLY PLACED MORTAR	22.000	SY
0570	523(A)3200	SEALER CRACK PREPARATION	78.000	LF
0580	523(B)3300	SEALER RESIN	2.000	GAL
0590	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	176.000	SF
0600	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	44.000	SY
0610	601(A)1110	TYPE I PLAIN RIPRAP	1,040.000	TON
0620	601(F)1600	TYPE IV GROUTED RIPRAP	850.000	SY
0630	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	74.000	LF
0640	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	52.000	LF
0650	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0660	619(B)6488	REMOVAL OF EXISTING RIPRAP	1.000	LSUM
0003	TRAFFIC			
0670	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	7.000	EA
0680	850(A)1200	SHEET ALUMINUM SIGNS	31.000	SF
0690	851(C)2430	2 1/2" SQUARE TUBE POST	65.000	LF
0700	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	8.000	EA
0710	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	1,358.000	LF

Proposal:270042 **Let Date:**January 21, 2027 **Call Order:**665
J/P Num:38369(04) **Proj. Num:**SBR-248C(066)SB
Counties:MARSHALL
Description:BRIDGE REHABILITATION
SH-32: OVER BRIAR CREEK, 1.8 MILES EAST
OF THE US-377 JUNCTION NEAR KINGSTON.
PROJECT LENGTH = 0.078 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL			
0720	871(B)2300	CONST.ZONE IMPACT ATTEN.	60.000	SD
0730	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	100.000	LF
0740	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	10,044.000	SD
0750	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,088.000	SD
0760	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,080.000	SD
0770	880(B)6330	CONSTRUCTION SIGNS 33.0 SF & OVER	216.000	SD
0780	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,260.000	SD
0790	880(E)6607	WARNING LIGHTS(TYPE B)	4,176.000	SD
0800	880(G)6800	TUBE CHANNELIZERS	1,728.000	SD
0810	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	328.000	SD
0005	STAKING			
0820	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0830	641 2110	MOBILIZATION	1.000	LSUM